

Procurement Office  
Harford Community College  
401 Thomas Run Road  
Bel Air Maryland 21015  
443.412.2307

**RFP 17P-002 AUDIO/VISUAL TECHNOLOGY EQUIPMENT INSTALL-EDGEWOOD HALL BUILDING**

ADDENDUM NO. 3

The following shall be incorporated into the captioned solicitation as though included in the original documents issued:

- .1 Scope of Work – Base Classroom Design, page 11, paragraph 5.2.2.2.10 - **ADD**
  - .a The College requests that the AVC use a good quality technology for the USB connection between the OFE PC and the OFE Epson 1430 WI Projector.  
Electrical flow example as follows:
    - .i Short USB connector from PC to a device to turn USB signal to Cat.x.
    - .ii A yellow Cat.x cable to wall plate that connects to a device that converts back from Cat.x at projector location to USB.
    - .iii A small Cat.x patch cord to connect from device to USB port on projector.
2. Page 10, paragraph heading 5.2.2 **CHANGE TO READ:**  
5.2.2 **Base Classroom Design – E143, E145, E146, E149, E157, E159, E207. E209, E219, E222, E223, E231, E232**
3. Page 11, 5.2.2.2 Scope of Work – Base Classroom Design **ADD:**  
Note: E157 is a split classroom and has two (2) projection systems-one in each half therefore E157 is considered as two (2) installs.
4. Page 11, paragraph 5.2.2.3 last sentence **CHANGE TO READ:**  
Rooms 159 and 161 will not be linked. Only one (1) projector is required in Room E159.  
Note: This shall be installed as a **Base Classroom Design**.
5. Page 13, paragraph heading 5.2.4 **DELETE** “Linked with room E161” and **ADD**  
Installation is the same as **Base Classroom Design** described in 5.2.2
6. Page 13, paragraph 5.2.4.2 Scope of Work-Lab E159 **DELETE** Entire Section.
7. Page 13, paragraph 5.2.4.3 Owner Furnish Equipment OFE **DELETE** Entire Section.
8. Page 14, **DELETE** Equipment Chart

## Questions / Answers

- Q1. This appears to be a request primarily installation and labor with equipment to be furnished by the university by the contractor. A.) How will the University be obtaining the equipment? B.) Will the contractor be allowed to submit a bid? C.) Who did the design for these classrooms? D.) Do drawings already exist? E.) How was the equipment list created?
- A1. A) & B) Yes this solicitation is for installation and labor only. Bidders may be required to provide limited equipment/materials as stated in Section 5 Detailed Specifications page 10. The College has already solicited bids for the equipment. Approval of the recommendation of that contract award will be placed on the Board of Public Works agenda shortly.  
C) The College.  
D) The only drawings are for the building renovation/addition developed by the project Architect.  
E) HCC standards
- Q2. Is there a budget amount for the Edgewood Hall project?
- A2. No budget figure is available; however, the project must be completed to support the renovation of Edgewood Hall. Renovation began January 2016 and will be completed December 2016.
- Q3. Could you please advise which low voltage certification is needed for installers? Would the Society of Broadcast Engineers-Certified Broadcast Technician certification qualify or does it need to be a specific certification from a specific organization?
- A3. Contact Harford County Department of Permits at 410-638-3344 to obtain this information.
- Q4. Will conduit be provided for the installation for Classroom 157 or will the AVC need to supply raceway for cabling?
- A4. A chase is available; see floor plan provided separately.
- Q5. Please provide an updated list of Classroom/Conference Room numbers. The room number between the RFP document and Addendum do not match.
- A5. The room numbers listed in #2 above are the correct numbers.
- Q6. Please provide part number for the Extron AAP plate that will be supplied with the Extron Cable Cubby 500.
- A6. The AVC shall provide the AAP Plate for installation. Follows are the Extron part numbers:
- 1 ea 70-101-13 -15-pin HD Female gender changer
  - 1 ea 3.5 mm Stereo Mini Jack to solder tabs
  - 70-090-12 Blank Plate-Double
  - 70-1065-04 Retractor HDMI
  - 2 ea 70-1065-35 Retractor Filler Mod CP
  - 70-1039-01 AAP\P Bracket

- Q7. Please clarify which signal output type will be used for the instructor's desktop PC.  
A7. HDMI
- Q8. Is the AVC responsible for the network configuration for the Epson 1430Wi project for Email, Storage and Printing functions? Will an IT resource be provided by HCC to assist with network/IP related information?  
A8. The College will configure projector network settings.
- Q9. Will the Epson whiteboard be installed by the GC or AVC?  
A9. The AV Contractor will install the whiteboards provided by the College.
- Q10. Will the Extron MLC 84 be powered by network POE or will power supplies be provided?  
A10: The power supply will be provided by the College.

**END ADDENDUM 3**

July 12, 2016